

**CITY OF MERCED  
PROJECT NO. 113026  
MUNICIPAL WELL 21 - WELL CONSTRUCTION**

**Bid Opening 1/4/18**

NO.	ITEM	UNIT OF MEASURE	ESTIMATED QUANTITY	Nor-Cal Pump & Well Drilling (Yuba City, CA)		Zim Industries, Inc. (Fresno, CA)	
				UNIT PRICE	ITEM TOTAL	UNIT PRICE	ITEM TOTAL
1	Mobilization and Demobilization (not to exceed \$30,000)	LS	1	\$ 30,000.00	\$ 30,000.00	\$ 30,000.00	\$ 30,000.00
2	Sound Attenuation	LS	1	\$ 29,700.00	\$ 29,700.00	\$ 14,000.00	\$ 14,000.00
3	34-Inch-Diameter Conductor Casing and 42-Inch-Diameter Bore Hole	VF	50	\$ 400.00	\$ 20,000.00	\$ 440.00	\$ 22,000.00
4	Temporary Discharge Pipe	LS	1	\$ 40,211.00	\$ 40,211.00	\$ 70,900.00	\$ 70,900.00
5	28-Inch-Diameter Well Production Hole	VF	590	\$ 90.00	\$ 53,100.00	\$ 97.00	\$ 57,230.00
6	Geophysical Logging of Well Bore Hole	LS	1	\$ 4,750.00	\$ 4,750.00	\$ 4,500.00	\$ 4,500.00
7	18-Inch-Diameter Stainless Steel Blank Well Casing	VF	273	\$ 440.00	\$ 120,120.00	\$ 447.00	\$ 122,031.00
8	18-Inch-Diameter Stainless Steel Louvered Well Casing	VF	370	\$ 585.00	\$ 216,450.00	\$ 596.00	\$ 220,520.00
9	Gravel Pack	VF	410	\$ 50.00	\$ 20,500.00	\$ 48.00	\$ 19,680.00
10	Annular Seal Including Bentonite Seal	VF	230	\$ 50.00	\$ 11,500.00	\$ 48.00	\$ 11,040.00
11	Airlifting and Swabbing	HRS	24	\$ 500.00	\$ 12,000.00	\$ 400.00	\$ 9,600.00
12	Setting and Removing Well Development Pump	LS	1	\$ 11,400.00	\$ 11,400.00	\$ 8,500.00	\$ 8,500.00
13	Well Development by Pumping and Surging	HRS	32	\$ 250.00	\$ 8,000.00	\$ 280.00	\$ 8,960.00
14	Pump Test	HRS	16	\$ 250.00	\$ 4,000.00	\$ 280.00	\$ 4,480.00
15	Miscellaneous Work	LS	1	\$ 26,576.00	\$ 26,576.00	\$ 47,000.00	\$ 47,000.00
					<b>\$ 608,307.00</b>		<b>\$ 650,441.00</b>